

Executive Engineer  
South Zone(Udhana)



Surat Municipal Corporation  
South Zone(Udhana)  
Opp. Satyanagar, Udhana,  
Surat.

☎2277043, 2278429.

QUOTATION INQUIRY-ONLINE

SZ/Tech./No.3746

Dtd.: - 23/07/2019

TO,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Sub: - Supply Erection Testing Commissioning of Audio System & Visual System for Auditorium located at First Floor of A.I.C. Surti I Lab-Smart City office, Near Rayka Circle @ South Zone (Udhna).

Dear Sir,

Sealed quotations duly super scribed the Subject Name and return on or before 02/08/2019 to the office of the undersigned is invited for supply, erection, testing & commissioning of following: -

Quotation

Sr. No.	Description	Unit	Qty.	Offered Make	Unit Rate (Including GST)	Total Amount (Including GST)
1	Supply, Installation, Testing & comissioning of 12" 2 way wooden design cabinet loudspeaker, 8Ω/350 Watts RMS Full range, opening angle 90°H x 70°V,IP 40 rating, frequency response 48 - 22K Hz, Max SPL 1mtr 127db with Necessary Wall Mounting Bracket (Make:- JBL/Bose/Bosch/Apart)	Nos.	2			
2	Supply, Installation, Testing & comissioning of 8" 2 way loudspeaker, 8Ω/300Watts full range,IP 40 rating, Max SPL 1mtr 112 db, frequency response 50 - 25K Hz, with necessary Wall Mounting Bracket (Make:- JBL/Bose/Bosch/Apart)	Nos.	6			
3	Supply, Installation, Testing & comissioning of Passive 2 x 10" subwoofer, 4ohm or 16Ω/2 x 600Watts, plywood construction with structured paint, black with necessary mounting arrangements (Make:- JBL/Bose/Bosch/Apart)	Nos.	2			
4	Supply, Installation, Testing & comissioning of Eight Channel Digital Power amplifier, 8 x 250Watts @ 4Ω, bridgeable to 4 X 500W @8 Ω, Class D, Convection cooled, Hypex inside, 1U 19" rackmount (Make:- JBL/Bose/Bosch/Apart/Crown/Celto)	Nos.	2			
5	Gooseneck Microphone: Supply, Installation, Testing & comissioning of Cardioid polar pattern; Frequency Response: 50 Hz to 20 kHz; Impedance <100 Ohms; Max Sound Pressure level: 130 dB; RF shielding against intermodulation from wireless devices with Shock mount (Make:-JTS/ Akg/ Shure/Sennheiser )	Nos.	2			
6	Wireless Handheld Microphone: Supply, Installation, Testing & comissioning of Frequency Response: 80 Hz to 16 kHz; Presets: 12; THD: <1%; S/N Ratio: > 103 dB(A), Microphone: Dynamic, SPL: 149 Db. (Make:-JTS/ Akg/ Shure/Sennheiser )	Nos.	2			
7	Wireless Headheld Microphone: Supply, Installation, Testing & comissioning of Frequency response: mic: 100 - 16000 Hz, Line: 60 - 16000 Hz; Presets: 12; THD: <1%; S/N Ratio: > 103 dB(A) (Make:-JTS/ Akg/ Shure/Sennheiser )	Nos.	2			
8	Wired Handheld Microphone: Supply, Installation, Testing & comissioning of Dynamic Cardioid polar pattern, Frequency Response: 40 Hz to 16 kHz; Sensitivity: 2,7 mV/Pa; Excellent feedback rejection;Rugged metal housing. (Make:-JTS/ Akg/ Shure/Sennheiser )	Nos.	2			

9	Mixing Console- Supply, Installation, Testing & comissioning of Mixing Console with 18 MIC/LINE inputs, 4 STEREO inputs; 4 STEREO AUX returns; 20Hz to 20kHz frequency response; THD+N 0.03%; S/N Ratio 114 dB; 3-band EQ with swappable MID Frequency on microphone channels; 4-band fixed EQ on stereo line channels; 4-GROUP MIX; 24-bit DSP effects for 100 presets (10 presets, 10 ariations); USB for computer software recording and monitoring; MP3 PLAYER, MP3 PLAYER/RECORDER or the BLUETOOTH Connection cards. (Make:- Soundcraft/Yamaha/RCF)	Nos.	1			
10	Microphone stand (Long): Supply & Installation of Light weight tripod alluminium Microphone stand with Long Arm, boom type & chrome plating. (Make:- k&M,Herculus/xtag)	Nos.	2			
11	Supply, Installation, Testing & comissioning of 5000 Lumens WUXGA PURE LASER Projector Min. 5,00,000:1 Contrast Ratio with Ceiling Mounted Stand(6 Feet Adjustable) (Make:- Sony/Epson/Panasonic)	Nos.	1			
12	Supply, Installation, Testing & comissioning of Projection Screen with necessary mounting arrangements: 220" Projector Motorised 16:9 aspect ratio (Make:- Avcraft/ Liberty/ Milestone/Da-lite/Draper)	Nos.	1			
13	Supply, Installation, Testing & comissioning of HDMI Switcher 4*2,4 HDMI Inputs and 2 HDMI Outputs , UltraHD / 4K @ 30Hz (2160p), FullHD @ 60Hz (Make:- Purelink/Kramer)	Nos.	1			
14	Supply, Installation, Testing & comissioning of HD BaseT Transmitter/Receiver Kit for Projector Support upto 70 metres 4K/UHD capability @ 60 Hz with 4:2:0 chroma subsampling HDCP 2.2 compliant (Make:- Atlona/Kramer)	Nos.	1			
15	Speaker Cable: Supply & laying of PVC insulated Cu conduction loudspeaker cable of 2 core 2. 5 Sqmm Make with PVC conduit (Make:- JVC/Finolex/Voltec/MX/Puralink)	Mtr.	200			
16	Supply, Installation, Testing & comissioning of 20 Mtrs. HDMI - HDMI Cable (Make:- Acer/MX/Lucido)	Nos.	2			
17	Supply, Installation, Testing & comissioning of 5 Mtrs. HDMI - HDMI Cable(Make:- Acer/MX/Lucido)	Nos.	2			
18	Rack: Supply, Installation, Testing & comissioning of Equipment Rack for housing all rack mountable equipments with internal wiring, front glass door; 2 nos, heat dessipation fans; movement wheels, 5 power distribution units etc. (Make:- Wallrack/ Rittal/ Dlink (16U))	Nos.	1			
Total Amount in Rs.						

☰ Terms/conditions of quotation ☰

*	Work Completion Period of entire SETC work :-	30 Days
*	Earnest Money Deposit:- (EMD)	15,000.00
*	All Taxes/Duties,GST,Octroi etc.: -	Included.
*	FOR: -	Auditorim at first floor of A.I.C. Surti I Lab, SEPC Center, Near Rayka Circle, South Zone(Udhana), S.M.C.
*	Validity of quotation: -	60 Days
*	Payment condition: -	Payment shall be made within 20 days after safe receipt, inspection/ testing and commissioning of material.
*	Note:-	Catalouge of offered make must be attached with Quotation. Bidders can not quote any items with other Makes mentioned in above quotation.

- Entire Sound/Audio System & Visual System must have 1 year warranty.
- Quantity mentioned here are approximate only. It may vary as per actual requirement.
- SMC will not pay any transportation charges and also not provide any type of assistance while carrying out above mentioned work. All accessories needed in installation of above mentioned items are in bidders scope only.
- Bidders are suggested to visit the site location of Auditorium before quoting this quotation and for any further query, bidder can contact Light department of South Zone, SMC.
- **The rates should be inclusive of all taxes/ duties,GST and Octroi.** Fulfillments of this condition are must or else the quotation shall be liable for outright rejection.
- **Rates must be filled in this quotation paper only and returned duly sealed & signed along with Earnest Money Deposit(EMD) of Rs. 15,000.00 in the form of crossed Demand Draft/ Pay Order of Nationalized/ Scheduled Bank acceptable to Corporation drawn in favour of the "Municipal Commissioner, Surat Municipal Corporation" payable at Surat.**
- The earnest money deposit will be refunded to the unsuccessful contractors after the award of work has been finalized.
- The earnest money deposit of the successful contractor shall be returned after the security deposite, as required, is furnished by the contractor.
- **Bank guarantee or cheque or FDR shall not be accepted for EMD.**
- The name of work i.e. “ **Quotation for the work of .....**” must be mentioned on the envelope without which quotation is likely to be rejected, which must be noted.
- For online, bidders can take print out of the Quotation and Submit to the undersigned office on or before **02/08/2019** at South Zone office in sealed envelope along with necessary documents as mentioned above. Address:- Executive Engineer, Administrative building, South Zone(Udhana), Opp. Satya Nagar, Udhana, Surat.

Thanking You,

-Sd-  
Executive Engineer,  
South Zone (Udhna),  
Surat Municipal Corporation.

**\* SIGNATURE & SEAL OF CONTRACTOR \***